

212 Orange Avenue Suffern, New York 10901

Phone: (845) 357-9300 | Fax: (845) 357-0966

August 14, 2018

\$1,310.00

Luke McCoy PLA, LEED Kaestle Boos Associates, Inc. 416 Slater Road New Britain, CT 06050-2590 PH: 860-259-1750 lmccoy@kba-architects.com

RE: Athletic Facilities Renovation Project - Derby High School, Derby, CT City Project No. COD 2018-02 (B) **Proposal for SKC - 1.1 Storm Water Revisions**

Dear Mr. McCoy,

As per your request the following proposal for changes made by Sheet SKC- 1.1 Storm Water revision as per your request. The following proposal includes the removal and disposal of 12" & 18" diameter RCP at an average 8' depth as identified at our last job meeting, removal and disposal of existing catch basins, installation of additional man holes, revisions to existing manholes due to increase in pipe diameter, and the installation of 15" HDPE solid and 10" HDPE perforated as per project plans and specifications. Proposal is as follows;

SKC - 1.1 Storm Water Revision

Description	Qty		<u>Unit</u>	
Demolition				
Rem. & Disp. CB	2.00	EA		
Backfill - M05.01/ Lifts/ Compacted	15.00	TN		
Total				
Rem. & Disp. 12" RCP, 8' avg. depth	260.00	LF	\$103.92 lf	
E 0.51 011 0.501/05 1.15 E	210.00	CIT /		

Kem. & Disp. 12 KCr, o avg. uepm	200.00	Lr	\$103.92 11
Exc. 3.5'w x 8'd x 260'/27 x 1.15 to Exp.	310.00	CY	
Rem. & load Dumpster - 12" RCP	260.00	LF	
Disposal - Concrete Dumpster	1.00	EA	
Backfill - M05.01/ Lifts/ Compacted	425.00	TN	
Testing	1.00	Day	
Trench box	1.00	LS	
Total			

\$27,021.40



Description	<u>Oty</u>		<u>Unit</u>	
Rem. & Disp. 18 " RCP, 8' avg. depth	320.00	LF	\$123.59 lf	
removal under proposed Synthetic Turf field				
Exc. 3.5'w x 8'd x 320'/27 x 1.15 to Exp.	382.00	CY		
Rem. & load Dumpster - 18" RCP	320.00	LF		
Disposal - Concrete Dumpster	2.00	EA		
Backfill - M05.01/ Lifts/ Compacted	523.00	TN		
Testing	2.00	Day		
Trench box	1.00	LS		
Total				\$39,548.80
Pipe & Structure Revisions				
Manholes	1	LS		
Deduct 30"Sq MH - No 3 & 4			\$1,457. ea	
Larger MH req. due to increase in pipe dia.				
30" Sq. Storm Manhole - 5.67 ' avg. depth	-2	EA		
Exc. 5.67'd x 7' x 7/ 27 x $1.15 =$	(24)	CY		
Structure w/ Casting	-2	EA		
Bedding - 3/4" crushed Stone	-2	TN		
Backfill	-19	CY		
Displacement	-5	CY		
Total				-\$2,914.00
Install				
4' dia. Manhole - 6.81 depth	1	EA		
Revised MH No. 3	20	OV.		
Exc. 7.31 'd x 8' x 8/ 27 x $1.15 =$	20	CY		
Structure w/ Casting	1	EA		
Bedding - 3/4" crushed Stone	1	TN		
Backfill	15	CY		
Displacement	5	CY		**
Total				\$2,454.00



Description	<u>Qty</u>		<u>Unit</u>	
5' dia. Manhole - 5.04' & 8.73' depths	2	EA		
revised MH No. 4 & 9	22	CV.		
Exc. 7.38'd x $10'$ x $10/27$ x $1.15 =$	32	CY		
Structure w/ Casting	2	EA		
Bedding - 3/4" crushed Stone	3	TN		
Backfill	24	CY		
Displacement	8	CY		φ = 22= 00
Total - \$2,668.50 ea				\$5,337.00
30" Sq. Storm Manhole - 7.83' avg. d MH No. 10 & 11	2	EA		
Exc. 8.33 'd x 6 x $6/27$ x $1.15 =$	26	CY		
Structure w/ Casting	2	EA		
Bedding 3/4" crushed Stone	2	TN		
Backfill	19	CY		
Displacement	7	CY		
Total - \$2,330.00 ea				\$4,660.00
				, , , , , , , , , , , , , , , , , , , ,
Deduct 12" HDPE	304.00	LF	\$49.43 lf	
Deduct 12" dia. HDPE, Solid, 5.48' avg.	-304	LF		
Exc.2 'w x 5.48'd x 337'l/ 27 x 1.15 =	-157	CY		
Inst 12" HDPE	-304	LF		
Bedding 3/4" crushed Stone	-212	TN		
Displacement to Export	-29	CY		
Total				-\$14,997.30
ADD 15" dia. HDPE, Solid, 5.48' avg. Stone to surface under pavement/field/ compacted	312	LF		
Exc. 3 'w x 5.48'd x 312'l/ 27 x 1.15 =	219	CY		
Inst 15" HDPE	312	LF		
3/4" crushed Stone Bedding to surface	229	TN		
Displacement to Export	176	CY		
Total				\$24,666.72



10" dia. HDPE, perf.	284	LF	\$80.03 lf
pipe under pavement/ gravel to surface/ compacted			
Exc. 2.833 'w x 5.89'd x 284'l/ 27 x 1.15 =	202	CY	
Inst 10" HDPE perf	284	EA	
Fittings	1	LS	
3/4" crushed Clean -2.833 x 5.167'd avg.	242	TN	
Filter Fabric	379	SY	
Displacement to Export	202	CY	
Total			<u>\$22,730.04</u>

Grand Total \$109,816.66

Please feel free to call if you should have any questions or required additional information.

Best regards,

Adam S. Horton

Adam Horton Estimator/ Project Manager Turco Golf, Inc. 430 Montclair avenue Pompton Lakes, New Jersey 07442 PH: 201-373-2385

CELL: 607-437-4672 ahorton@grasskeepers.net



